BRUHAT BENGALURU MAHANAGARA PALIKE

Construction of CC roads and other works at Chikkasandra colony in ward No.12, Shettyhalli Sub-division
Ward No. 12 - Shettyhalli.
Sl. No. 01, G O No. 83 (Package No - DHZ 01)

DRAFT TENDER SCHEDULE - B

ESTIMATED COST – 99.00 LAKHS | **JOB CODE: 012-20-000010**

Sl. No.	Description of Work	Unit	Quantity	Rate in Rs.
1	KSRRB M200-13.1. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. II. By Mechanical Means. A. Cement Concrete Grade M-15 &M-20. MORTH Specification No. 202 All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	161.10	413.40
2	Removing B.S. slab of Drain and stacking. (PW,P& IWTD SR 2018-19, Pg No 27 Item No.5.32).	Sqm	537.00	104.94
3	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH I Chapter 3. All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	728.21	137.80
4	KSRB 4-1.7: Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 ems. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	132.46	5714.97
5	KSRRB M2200-5.12. Providing and laying Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.7 cum and fine aggregates @ 0.47 cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008. i) Upto 5 m height. All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	225.54	5775.37
6	KSRRB M2200-6. Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200 -do- TMT Bars Fe 500 All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Tonne	13.53	72,326.98

ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ: Nil
ರದ್ದುಗೊಳಿಸಿರುವ ಐಟಂಗಳ ಸಂಖ್ಯೆ: Nil
Scelly
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು

CONTRACTOR

EXECUTIVE ENGINEER
KR PURAM, BBMP DIVISION
BENGALURU-560 016

EXECUTIVE ENGINEER
DASARAHALLI DIVISION
BBMP

7	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortor including form work, lift charges , curing and concrtee finished surface on both sides etc, and complete as per the directions of Enginner in charges. (Data Rate) All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Sqm	644.40	1615.00
8	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials separately complete as per specifications. MORTH Specification No. 202 All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	194.12	952.94
9	KSRRB 300-48. Scarifying kankar / gravel / metal crust by mechanical means upto 150mm thick, disposal of stuff including cost of all labour charges, HOM complete as per specifications. MORTH / Chapter 3 All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Sqm	1941.20	25.44
10	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications. MORTH I Chapter 3 All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Sqm	1941.20	6.36
11	KSRRB M600-1.Providing and Constructing dry lean cement concrete mix CC 1:5:10 base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @0.58cum over a prepared sub-base, coarse and fine aggregate conforming to IS: 383-2016,aggregate cement ratio not to exceed 15:1, Aggregate gradation after blending to be as per Table 600-1 ,optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a hatching plant, transported to site,laid with a paver, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. Clause 601of MORTH V Revision and IS 456 Table-5 -do- with OPC at 150 kg/cum and coarse aggregate 0.86cum, fine aggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with fixed form paver. All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	194.12	3944.51
12	KSRRB M400-17. Providing, laying, spreading and compacting Crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No.406. All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	194.12	2001.28

ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ:.....

ರದ್ದುಗೊಳಿಸಿರುವ ಐಟಂಗಳ ಸಂಖ್ಯೆ:.....

ತಾಂತ್ರಿಕ ಸಹಾಯಕರ

CONTRACTOR

EXECUTIVE ENGINEER-
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEE
DASARAHALLI DIVISI
BBMP

13	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to18:383-2016, with Superplastizer at 3 Its conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades,textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per specifications. -do- with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	310.59	5354.02
14	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Nos	1591.00	435.84
15	KSRRB M800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications,MORTH Chapter 8 All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Sqm	250.60	84.80
16	KSRRB M300-19 Removal of unserviceable soil including excavation, loading and disposal but excluding replacement by suitable soil which shall be paid separately as per clause 300.5 complete as per specifications MORTH Specification No. 301. (All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	728.21	34.98
17	KSRRB M-100-1 Loading and Unloading of Stone Boulder / Stone aggregate / Sand Kanker / Moorum.KSRRB M100-1 : Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications.MORTH -100 / Chapter 1, All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	646.40	57.00

ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ: Nil

ರದ್ದುಗೊಳಿಸಿರುವ ಐಟಂಗಳ ಸಂಖ್ಯೆ: Nil

ತಾಂತ್ರಿಕ ಅಧಿಕಾರಿ

EXECUTIVE ENGINEER
KRIDL, BBMP DIVISION
BENGALURU-560 010

CONTRACTOR

EXECUTIVE ENGINEER
DASARAHALLI DIVISION
BBMP

18	KSRRB M100-4.1. Cost of haulage Excluding Loading and Unloading MORTH-100/Chapter 1 case-I surface road (All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Cum	1374.61	71.68
19	Filling in foundation with granite/trap broken metal 100mm and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead up to 50m and lift 1.5m complete as per specifications. All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.			
	a) 40mm Jelly.	Cum	1.12	1901.00
	b) 20mm Jelly.	Cum	1.12	1901.00
	c) Coarse sand.	Cum	0.84	2651.00
	d) Fine Sand	Cum	0.56	2651.00
	e) 12.5mm chips	Cum	0.84	1901.00
20	Supplying, laying and jointing HDPE pipes of specified grade and conforming to IS 4984- 995 with latest amendments and conveyingto work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bends, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc. for : HDPE Grade PE80-PN6.0, 630 mm dia. **(Perforated Pipe for Rain Water Harvesting Pit)** All lead amd lift complete as per specification and as per the directon of the engineer in charge of the site.	Rmt	16.20	10822.32
21	Providing of Geonets for Rain Water Harvesting pit on top of the filter media as specified in drawings or as approved by Engineer Incharge.	Sqm	2.81	71.03

ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ:-Nil-
ರದ್ದುಗೊಳಿಸಿರುವ ಐಟಂಗಳ ಸಂಖ್ಯೆ:-Nil-
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು

ಕಂಡಿಕೆ(23)ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು(ದಾಸನಹಳ್ಳಿ)ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಷರತ್ತಿಗ ಒಳಪಡಿಸಿ ಡಿ.ಟಿ.ಎಸ್
ಅನುಮೋದಿಸಿದೆ.
ಕರದು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ:-Nil-
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಂಗಳ ಸಂಖ್ಯೆ:-Nil-
16/11/2019
ಮುಖ್ಯ ಅಭಿಯಂತರರು (ದಾಸರಹಳ್ಳಿ).

EXECUTIVE ENGINEER-
KRIDL, BBMP DIVISION
BENGALURU-560 010

CONTRACTOR

EXECUTIVE ENGINEER
DASARAHALLI DIVISION
BBMP